



QUALITY STONE

TAKE-OFF SHEET



1. Starter Strips

Perimeter of area to be covered _____ feet / 4 = _____ pieces of Starter Strips.

(Starter strip comes in 48" lengths, and are required under each panel on the bottom course)

2. Corners

Total height of all corners to be covered _____ feet x 2 (Ledge/Stacked Stone) = _____ Corner Panels.

Total height of all corners to be covered _____ feet x 1 (Castle and Tile Stone) = _____ Corner Panels.

(Ledge Stone and Stacked Stone Corners are 6" in height and 40" in length. Castle Stone and Tile Stone Corners are 12" in height and 40" in length. There are Right and Left Corner Panels, which should be alternated on each corner)

3. Trims

Total Perimeter / height to be covered _____ feet / 4 = _____ Edge Trims.

(Edge Trims are 48" in length, and are used for the sides and top of windows and door openings, and as an optional vertical finishing edge at the end of a row panels)

Total length to be covered _____ feet / 4 = _____ Ledge Trims.

(Ledge Trims are 48" in length and are used for the bottoms ledge of windows and as a horizontal finishing ledge above panels)

4. Panels

a) Total width of the area to be covered = _____ feet / 4 (Panels are 48" in length) = _____ Panels.

b) # of courses...

Total height to be covered = _____ feet x 2 (Ledge Stone and Stacked Stone) = _____ Panels.

(OR)

Total height to be covered = _____ feet x 1 (Castle Stone and Tile Stone) = _____ Panels.

c) Multiply a) x b) = _____ # of panels. Allow for up to 5% waste.

5. Fastening

2" Screws _____. 3" Screws _____.

(2" deck screws are recommended for starter strip, panel and corner installation. 3-4" deck screws are recommended for Edge and Ledge Trim installation. Approx. 6 screws per starter strip and panel, and 4 screws per trim)

Adhesive _____.

(Use a premium (polyurethane friendly) adhesive such as Chemtrex 948, Titebond Heavy Duty Construction Adhesive, PL Premium). Refer to Installation Instructions to if adhesive is needed (installing on concrete, brick, etc.)

Trim Mounting Brackets _____.

(Edge and Ledge Trim can be mounted using mounting brackets – as an alternative to face-screwing the trims. This is recommended for installations where (new) siding or stucco can be used to cover the mounting bracket)

6. Accessories

Stone Finish (textured caulking) _____.

(12 oz. tubes cover about 120 square feet per tube. Different stone colors will require different combinations of caulking colors. Please refer to the Stone Finish Matrix PDF for to ensure you have the proper colors)

Paint Touch-Up Kit _____.

(Touch-up kits contain (4) 4 oz. bottles of paint-one for each color palette used in the panel and a brush)

Stagger Stencil _____. Only (1) is needed, and can be used many times.

(Used to make a 'staggered' cut in the middle of a panel so that the end fits into a factory stagger)